

LAB ENGINEERING REPORT: ETHERCHANNEL & INTER-VLAN ROUTING

Engineer: Eng: Mohamed Ashraf Focus: Two-Tier Collapsed Core Design Date: June 2026

1. Executive Summary

This technical engineering report chronicles the successful configuration, optimization, and validation of a high-availability, multi-tiered enterprise campus network environment simulated within Cisco Packet Tracer. The topology incorporates advanced Layer 2 and Layer 3 EtherChannel bundling protocols (LACP and PAgP), combined with multi-layer Inter-VLAN routing and static route optimization. This document is formatted to serve as an enterprise-grade reference architecture for network portfolio deployment.

2. Network Topology & Segment Specifications

The network topology transitions from an access layer composed of dedicated Layer 2 switches to a distribution tier built upon high-performance Layer 3 Multilayer Switches (DSW1 and DSW2). Below is the precise logical schema defining the operational network blocks:

Network Segment	Subnet Range	VLAN Assignment	Default Gateway SVI	Connected Hosts
Red Zone (Access)	172.16.1.0/24	VLAN 1	172.16.1.254 (DSW1)	PC1 (.1), PC2 (.2), PC3 (.3)
Green Zone (Access)	172.16.2.0/24	VLAN 1	172.16.2.254 (DSW2)	SRV1 (.1), Laptop (.2)
Blue Zone (Core Routing)	10.0.0.0/30	Routed Port-Channel 20	N/A (Point-to-Point)	DSW1 (.1), DSW2 (.2)

3. Device Configuration Blueprint & Verification

3.1. Access Switch 1 (ASW1) Configuration

ASW1 aggregates traffic from the user computers and uplinks to DSW1 via a Layer 2 LACP EtherChannel configured explicitly as an IEEE 802.1Q trunk link.

```

ASW1# configure terminal
ASW1(config)# interface range g0/1 - 2
ASW1(config-if-range)# channel-group 1 mode active
ASW1(config-if-range)# exit
ASW1(config)# interface port-channel 1
ASW1(config-if)# switchport trunk encapsulation dot1q
ASW1(config-if)# switchport mode trunk
ASW1(config-if)# exit
ASW1(config)# port-channel load-balance src-dst-ip

```

Verification State - ASW1 (Command: show etherchannel summary)

Group 1 | Port-channel: **Po1 (SU)** | Protocol: **LACP** | Ports: **Gig0/1(P) Gig0/2(P)** **ACTIVE / IN-USE**

3.2. Distribution Switch 1 (DSW1) Configuration

DSW1 operates as the default gateway for the Red Zone. It runs global IP routing, manages an L2 trunk bundle to ASW1, and routes traffic over a Layer 3 static EtherChannel bundle directly into DSW2.

```

DSW1# configure terminal
DSW1(config)# ip routing
DSW1(config)# interface range g1/0/3 - 4
DSW1(config-if-range)# switchport trunk encapsulation dot1q
DSW1(config-if-range)# switchport mode trunk
DSW1(config-if-range)# channel-group 1 mode active
DSW1(config-if-range)# exit
DSW1(config)# interface port-channel 1
DSW1(config-if)# switchport trunk encapsulation dot1q
DSW1(config-if)# switchport mode trunk
DSW1(config-if)# exit
! --- Core L3 EtherChannel Assembly ---
DSW1(config)# interface range g1/0/1 - 2
DSW1(config-if-range)# no switchport
DSW1(config-if-range)# channel-group 20 mode on
DSW1(config-if-range)# exit
DSW1(config)# interface port-channel 20
DSW1(config-if)# ip address 10.0.0.1 255.255.255.252
DSW1(config-if)# exit
! --- Routing Protocols & Gateways ---
DSW1(config)# interface vlan 1
DSW1(config-if)# ip address 172.16.1.254 255.255.255.0
DSW1(config-if)# no shutdown
DSW1(config-if)# exit
DSW1(config)# ip route 172.16.2.0 255.255.255.0 10.0.0.2
DSW1(config)# port-channel load-balance src-dst-ip

```

Verification State - DSW1 (Command: show etherchannel summary)

Group 1 | Port-channel: **Po1 (SU)** | Protocol: **LACP** | Ports: **Gig1/0/3(P) Gig1/0/4(P)**

Group 20 | Port-channel: **Po20 (RU)** | Protocol: **- (Static)** | Ports: **Gig1/0/1(P) Gig1/0/2(P)** **ROUTED UP**

3.3. Access Switch 2 (ASW2) Configuration

ASW2 aggregates the server tier using Cisco proprietary PAgP trunk framing to connect reliably into the distribution block.

```
ASW2# configure terminal
ASW2(config)# interface range g0/1 - 2
ASW2(config-if-range)# channel-group 2 mode desirable
ASW2(config-if-range)# exit
ASW2(config)# interface port-channel 2
ASW2(config-if)# switchport trunk encapsulation dot1q
ASW2(config-if)# switchport mode trunk
```

3.4. Distribution Switch 2 (DSW2) Configuration

DSW2 mirrors DSW1's capabilities, processing the gateway SVIs for the servers and laptop, and maintaining static routes back to the user network tier.

```
DSW2# configure terminal
DSW2(config)# ip routing
DSW2(config)# interface range g1/0/3 - 4
DSW2(config-if-range)# channel-group 2 mode desirable
DSW2(config-if-range)# exit
DSW2(config)# interface port-channel 2
DSW2(config-if)# switchport trunk encapsulation dot1q
DSW2(config-if)# switchport mode trunk
DSW2(config-if)# exit
! --- Core Link ---
DSW2(config)# interface range g1/0/1 - 2
DSW2(config-if-range)# no switchport
DSW2(config-if-range)# channel-group 20 mode on
DSW2(config-if-range)# exit
DSW2(config)# interface port-channel 20
DSW2(config-if)# ip address 10.0.0.2 255.255.255.252
DSW2(config-if)# exit
! --- SVI & Static Routes ---
DSW2(config)# interface vlan 1
DSW2(config-if)# ip address 172.16.2.254 255.255.255.0
DSW2(config-if)# no shutdown
DSW2(config-if)# exit
DSW2(config)# ip route 172.16.1.0 255.255.255.0 10.0.0.1
DSW2(config)# port-channel load-balance src-dst-ip
```

4. Deep-Dive Troubleshooting & Structural Resolutions

During lab development, severe end-to-end communication failures (100% ICMP packet drops) were encountered. Below is the documentation of how those logical errors were isolated and structurally resolved:

Incident 1: Inactive Route Table due to Logical Port Mismatch

Symptom: Executing `show ip route` on DSW1 returned an entirely empty routing table.

Root Cause Analysis: The Layer 3 point-to-point EtherChannel was physically established under `Port-channel 20` (matching DSW2), but the IP configurations and static routes were mistakenly assigned onto a non-existent interface `Port-channel 12`. Because the interface was logically down, the routing table flushed all paths.

Resolution Code implemented: Removed the IP configuration from `Po12` and reassigned it explicitly to `Po20`.

Incident 2: SVI Administratively Closed Status

Symptom: Systems could not reach their default gateway, and log output displayed `Interface Vlan1, changed state to administratively down`.

Root Cause Analysis: Packet Tracer occasionally experiences a state-machine lag during heavy configuration changes on multilayer trunk bundles, locking the SVI into a structural shutdown loop.

Resolution Code implemented: Triggered a forced manual flap (shutdown followed by no shutdown) under the `interface vlan 1` configuration block. This synchronized the physical trunking state with the Layer 3 SVI database, immediately changing the line protocol status to **Up/Up**.

5. Connectivity Matrix & Load-Balancing Analysis

5.1. Lab Question 5: Default Load-Balancing Architecture

On standard Cisco Catalyst platforms simulated within Packet Tracer, the out-of-the-box default load-balancing behavior is highly hardware-dependent:

- Layer 2 Access Switches (e.g., 2960) leverage **Source MAC Address hashing (src-mac)**.
- Layer 3 Multilayer Switches (e.g., 3650) leverage **Source IP Address hashing (src-ip)** or combined metrics.

Optimization (Step 6 Implementation): To avoid link polarization (where one link is overutilized while the other sits idle), the system-wide hashing calculation on both distribution switches was optimized via the global command `port-channel load-balance src-dst-ip`. Traffic distribution is now dynamically generated using a cryptographic XOR logic processing both the packet's source IP and destination IP.

5.2. Verification Matrix

Following structural synchronization, complete connectivity validation was verified across the network boundaries via ICMP:

Origin Node	Destination Node	Target IP Address	ICMP Success Rate	Behavioral Analysis
PC1	SRV1 (Server)	172.16.2.1	50% SUCCESS (2/4 Recv)	Initial drops are expected standard behavior. Packets are dropped while DSW1 resolves ARP requests across the Layer 3 transit link.
PC1	Laptop	172.16.2.2	100% SUCCESS (4/4 Recv)	Perfect link utilization. Subnet structures are completely cached in the distribution CEF tables.
Laptop	PC3	172.16.1.3	75% SUCCESS (3/4 Recv)	Single drop due to local destination access link ARP tracking on ASW1. Subsequent frames transmit immediately.

Sign-off & Engineering Verification

All parameters outlined within the lab brief have been systematically completed, tested, and vetted. The collapsed-core multi-layer architecture is verified stable and running optimally.